

GEOCELL® FOAM GLASS GRAVEL

DELIVERY AND INSTALLATION

BULK LOOSE MATERIAL – Max 90m³

Walking floor truck – 18m x 2.5m x 4m



Pre-packed Bigbags – Max 66m³

Walking floor truck – 18m x 2.5m x 4m



Pre-packed Bigbags – 16m³ per load

Crane off load – Local delivery only



Pre-packed Bigbags – Qty as required

Pallet distribution network



Bigbags Sizes

BigBag 1 m³ ~ 150 kg

BigBag 2 m³ ~ 300 kg

BigBag 3 m³ ~ 450 kg



Compaction Factor 1.3:1

Light vibration plate with strong drive

Running weight <100 kg

Frequency > 85 Hz, centrifugal force <18 kN



Compaction Factor 1.3:1

Medium-weight, non-propelled and self-propelled rollers

Running weight <7.5t, static line loads ~ 20 kg / cm

Frequency > 65 Hz



Compaction Factor 1.6:1

Medium vibration disk with strong propulsion

Running weight <500 kg

Frequency > 65 Hz, centrifugal force 18 kN <60 kN



Compaction Factor 1.6:1

Vibrating roller with 2500 kg operating weight



Compaction Factor 1.6:1

Stamping device with adjustable force input